PERFORMACE REPORT OF AJAX SELF LOADING CONCRETE MIXER - "ARGO 4000"

TEST ORDER NO. BL/193/8/2019/2 Dated: 02.08.2019

OCTOBER 2019

REPORT FOR

M/s. Ajax Engineering Pvt. Ltd. #253/1, 11th Main, Phase III, Peenya Industrial Area, Bengaluru - 560 058, Karnataka, India.



BUREAU VERITAS (INDIA) PRIVATE LIMITED

Construction Services Laboratory
43, 45, 46 & 47, Ground & 1st Floor, 1st Main, Pete Chennappa Inds. Estate, Magadi Road,
makshipalya, Bangalore 560 079





Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2 Dated : 02.08.2019

CONTENTS

- A. INTRODUCTION
- **B. DETAILS OF MATERIALS**
- C. PROCEDURE FOR BATCHING MATERIALS
- D. DESIGN MIX AND DETAILS OF TRIALS CONDUCTED
- E. INFERENCES
- F. CONCLUSION
- G. REFERENCES

APPENDIX

PHOTOGRAPHS

BUREAU VERITAS (INDIA) PRIVATE LIMITED

Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

A. INTRODUCTION:

On reference from M/s. Ajax Engineering Pvt. Ltd., #253/1, 11th Main, Phase III, Peenya Industrial Area, Bengaluru - 560 058, Karnataka, India, vide their Letter Dated 03.07.2019. Performance of Self Loading Concrete Mixer "ARGO 4000" was taken up at a site vide our Test Order No. BL/193/8/2019 Dated: 02.08.2019.

For evaluating the performance of self-loading concrete mixer, trials were conducted by adopting a theoretically proportioned concrete mix based on IS-10262-2019 and IS-456-2000 recommendations.

B. MATERIALS:

Cement

Dalmia, SRPC

Aggregates

:

:

Fine Aggregate

Manufactured sand

Coarse Aggregate

Angular crusher broken coarse aggregate of

size 20 mm and 12.5 mm.

Materials adopted during trials are conforming to relevant Indian Standards.



Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

<u>DETAILS OF AJAX SELF LOADING CONCRETE MIXER: -</u> <u>"ARGO 4000"</u>

Specification: (As furnished by the customer)

Engine

- 4 Cylinder turbo charged intercooled 80.9 kW @ 2500 rpm.
- Bharat III Emission Certified

Chassis

High tensile steel welded "Box" type construction

Hydrostatic Drum Drive

- Hydrostatic Drum Drive with high rotation for homogenous mix and drum lift for fast and complete discharge even on inclines.
- Drum Volume: 5.3 m³
- Concrete Output : 4m³
- Maximum Drum Rotation : 0 − 22 rpm
- Infinitely variable for mixing & discharge.

Wheels

• Tyre: 16.0/70-20 -14 PR

Transmission

- 4 wheel drive, 4 Speed Automotive hydrostatic transmission.
- Electro-hydraulic control for "slow" & "fast" speeds.
- Vehicle speed 0 to 30 Kmph (forward and reverse)

Brake

- Wet discs available in front & rear axles.
- Hand operated parking brake acting on transmission shaft.

Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.


Electrical System

- Battery: 12V, 135 Amp-hr.
- Complete lighting & signalling system as per CMVR standards.

Weight

• Net vehicle weight: 7610 kgs

• Gross vehicle weight :17210 kgs



C. PROCEDURE FOR BATCHING OF MATERIALS:

Trained operator of the self-loader uses mix design recipe for batching the materials. Concrete Batch Controller (CBC) fitted inside the operator cabin, aids the operator to know the weight of the aggregate batched. Loading is continued until the required quantity is batched.

Construction Services Laboratory No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area, Magadi Main Road, Kamakshipalya, Bangalore - 79

NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2

Dated: 02.08.2019

Aggregate is scooped by the loading bucket and loaded into the mixer. Similarly required quantity of cement is batched using loading bucket. Water is added to the mixer

from the water tank fitted with a water meter. After batching all the constituents of

concrete, the mixer is kept rotating.

Print out of the batched materials can be obtained using a batch printer fitted in the cabin.

D. DESIGN MIX AND DETAILS OF TRIALS CONDUCTED

Trials were conducted for M25 grade of concrete in the self loading Ajax mixer-

"ARGO-4000" machine.

T. MIX DESIGN ADOPTED

TRIAL -1:

Cement - 350 kgs

W/C - 0.49

Water - 171.5 kgs

Manufactured Sand – 780.5 kgs

20 mm - 638.5 kgs

12.5 mm - 425.6 kgs

II. **CONTROL MIX:**

Trial was done with Control Concrete (without Chemical Admixture), Concrete samples were

collected while unloading, one sample collected in the beginning and 2nd sample was collected in

the middle and 3rd Sample collected at the end, to check the consistency of concrete mix in the

same batch. Cubes were cast for determining the compressive strength at 7 days and 28 days.

Page 5 of 10



Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

TABLE - I

Fresh & Hardened Concrete Properties

Sample No.	(Workability) Slump (mm)	Compressive Strength of Concrete in N/mm ²	
		7 days	28 Days
Sample-1	70	24.9	32.8
Sample-2	50	25.8	33.5
Sample-3	45	26.5	34.9



Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79
NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

E. INFERENCES:

- 1. Calibration of batching systems was done, as informed by customer.
- 2. Mixing of concrete is achieved by rotation of mixer at a predetermined speed.
- 3. The concrete mix was found to be satisfactory in terms of workability. The increase in slump can be obtained by adding admixture.
- 4. Concrete mix was found to be satisfactory at different points in the mixer during unloading.
- 5. Cube Compressive strength of concrete was found to be satisfactory meeting the requirement of 28-day strength in all trials.

F. **CONCLUSION**:

The performance of self-loading concrete mixer "ARGO 4000" was found to be satisfactory in terms of homogeneity, cohesiveness, workability and compressive strength of concrete produced

22 10/2019 SANJEEV PATGAR Manager Lab



BUREAU VERITAS (INDIA) PRIVATE LIMITED

Construction Services Laboratory
No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,
Magadi Main Road, Kamakshipalya, Bangalore - 79

NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2 Dated: 02.08.2019



AJAX Argo 4000 machine



Loading of Cement through AJAX ARGO 4000



BUREAU VERITAS (INDIA) PRIVATE LIMITED

Construction Services Laboratory

No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,

Magadi Main Road, Kamakshipalya, Bangalore - 79

NABL Accredited Laboratory as per ISO 17025

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

Test order No. BL/193/8/2019/2 Dated: 02.08.2019



Loading of Manufactured Sand through AJAX ARGO 40000



Loading of Coarse aggregate through AJAX ARGO 40000



BUREAU VERITAS (INDIA) PRIVATE LIMITED

Construction Services Laboratory

No. 43,45,46 & 47, Ground & 1st Floor, Pete Chenappa Industrial Area,

Magadi Main Road, Kamakshipalya, Bangalore - 79

NABL Accredited Laboratory as per ISO 17025

Test order No. BL/193/8/2019/2 Dated: 02.08.2019

To: M/s Ajax Engineering Pvt. Ltd., Bengaluru.

G.	REFERENCES:		
1.	IS:10262-2019	Concrete Mix Proportioning - Guidelines (Second Revision)	
2.	SP:23(S&T)-1982	Handbook on concrete mixes.	
3.	IS:456-2000 (Reaffirmed 2016)	Code of Practice for plain & reinforced concrete. (Fourth Revision)	
4.	IS:516-1959 (Reaffirmed 2013)	Method of test for strength of concrete.	
5.	IS:383-2016	Indian Standard specifications for coarse and fine aggregates for concrete. (Third Revision)	
6.	IS:1199-1959 (Reaffirmed 2013)	Indian Standard specifications for methods of sampling and analysis of concrete.	
7.	IS:1199-2018 (Part 1)	Indian Standard specifications for methods of sampling and analysis of fresh concrete.	
8.	IS:4926-2003 (Reaffirmed 2017)	Ready-Mixed Concrete - Code of Practice	
9.	IS: 12330 – 1988 (Reaffirmed 2009)	Sulphate Resisting Portland Cement	
10.	Neville, A. M.	"Properties of Concrete" 4 th Edition, – 1995- Publicity Pearson Education (Singapore) Pte. Ltd., Indian Branch, 482, FIE, Prathapganj Delhi 110092	